

EXAMPLE AIR TESTING CO. MOLD INSPECTION REPORT

Property: 100 Sample Way, Apt. 4, Oakland, CA

Client: Roe Holdings, LLC

Date of inspection: March 3, 2026

Inspector: R. Sample, Certified Mold Inspector

Findings

Bathroom ceiling: visible growth, about 6 square feet.

Bedroom wall shared with bathroom: visible growth,
about 4 square feet; moisture reading 38 percent.

Air sample, bathroom: 14,200 spores per cubic meter.

Air sample, bedroom: 9,800 spores per cubic meter.

Outdoor control sample: 1,100 spores per cubic meter.

Conclusion

Indoor spore counts exceed the outdoor control. The
source is an active leak above the bathroom ceiling.
Repair the leak, then remove affected drywall.

Report delivered to client March 3, 2026.

Fictional document generated for the Cursitor example.